

# **TRIO**

The most successful panel formwork with only one connecting component



TRIO-L Alu
TRIO 330
TRIO Structure
TRIO Column

#### Edition 03/2010

## PERI GmbH Formwork Scaffolding Engineering

P.O. Box 1264 89259 Weissenhorn Germany Tel +49 (0)73 09.9 50-0 Fax +49 (0)73 09.9 51-0 info@peri.com www.peri.com

# Important Notes:

Without exception, all current safety regulations must be observed in those countries where our products are used.

The illustrations in this brochure are photographs of particular situations on a construction site. Safety or formwork anchor details are therefore not to be taken as a definitive guide to the way the equipment is to be used.

Safety precautions and allowable loads are to be strictly observed at all times. Separate structural calculations are required for any deviations from the standard design data.

The information contained herein is subject to technical changes in the interests of progress. Errors and typographical mistakes reserved.


_	
Contents	Page
The illustrated essentials	
Europe's most successful panel formwork	1
The BFD Alignment Coupler	2
The large panel	4-5
Details that cut labour costs	6-7
TRIO is the system for all applications	8-9
PERI offers more than just the formwork	10-11
General applications	
Standard details	12-13
Care, cleaning and maintenance	14-17
Transportation, Handling and Storage	18-19
Safety from the outset	20-21
Safe Concreting	22-23
<u> </u>	
Special applications	
Foundations	24-25
Single face walls	26-27
Shafts	28-29
High Walls	30-31
Circular Structures	32-33
Climbing Formwork	34-35
Special Applications	36-37
TRIO add-on systems	
TRIO-L (aluminium)	38-39
TRIO 330	40-41
TRIO Structure	42-43
TRIO column formwork	44-45
Components	46-75
PERI International	76-77



The continuing rise in site labour costs necessitates ever faster and simpler formwork systems, for the following reasons:

Most of the expenditure on a reinforced concrete frame is down to the shuttering work, where labour costs exceed material costs several times.

The number of individual parts to be moved determines the shuttering time and hence costs.




Cost of a 300 mm thick concrete

The pie chart shows that almost 50% of the total costs are down to formwork labour. Reducing this contribution is the most effective way of improving your bottom line.

# There has to be a reason why PERI TRIO has become the most successful panel formwork

TRIO can be used **On small** ...

PERI's development engineers have focused on minimising the shuttering costs and the number of individual components.



Only 6 panel widths for any layout





The BFD is the only coupler required.

#### ... and large sites



Standard panel joint

External and internal corners

Height extensions








# Just 1 component for all connections The BFD Alignment Coupler



Articulated corners







Spanning filler timbers up to 100mm thick




acronym for fastening, aligning and tightening in a single operation.

Holding plywood fillers



Acting as a clamp







Panel extensions

Timber extensions

# The BFD alignment coupler allows all departments to achieve their objectives faster and hence more cost-effectively:

# Design,

because just one multi-purpose component allows quicker design and equipment scheduling.

## The yard,


because just one multi-purpose component simplifies stocking and prevents delivery errors.

#### The site,

because just one multi-purpose component avoids time-consuming searching and sorting.

# The angle of the engagement slot is a special feature of the BFD connection.

It directs the clamping force, fastens, aligns and tightens in that order.



# Holding stopends






Combining TRIO with RUNDFLEX




Combining TRIO with SRS circular column formwork




Connection of external vibrators



The large ( $2.70 \times 2.40$ m) panel with internal tie holes.



# The large panel with 2 heights and 2 widths



Extension **without** additional extension panels.

# The large (2.70 x 2.40m) TRIO panel has major advantages:

# 2 heights and 2 widths

for maximum utilisation of the full area of the panel

# Internal tie points

no plugging of tie holes, simple stopends and wall junctions

# **High structural stiffness**


reduces deflection


# Orderly pattern of joints

no extension panels required

# Optimum size for transportation


2.40m wide panel fits on any lorry





#### **T-junctions**

90 panel and internal corner only for any wall thickness



# Only 6 panel widths for any layout


**PERI TRIO requires only** 6 different panel widths


**Practical 300mm** increments in panel size:

2.4m wide panel 1.2m wide panel 0.9m wide panel 0.6m wide panel 0.3m wide panel


and the 720mm wide TRIO panel reduce stocks and increase utilisation.

TRIO does not require any special corner panels. The 600 and 720mm panels needed for corners can also be used in straight walls.











Typical example of modern housing construction: oblique angles, returns and different wall thicknesses.



Standard panels for circular structures



Panels being used on their side for foundations




TRIO panels on their side and extended to a height of 6.0m

#### **ECC** powder coating

prevents concrete adhesion and makes cleaning easier.



Patented tie holes allow tie points blocked with concrete to be cleared easily, since TRIO panels have tapered plastic sleeves that pass right through the frame




to allow DW 15 tie rods **angled** at 6° in any direction, as well as the use of the DW 20 tie rod.



#### Levering corners

make it possible to move the panel into position without using a hammer.




#### **Closed panel sections**

ensure high torsional stability and are easy to keep clean.


#### Struts all round

allow the TRIO panels to be used upright or on their sides, and ensure a stiff connection for extensions.

Special TRIO features
Details that cut labour costs



The life of a form and speed of shuttering are substantially improved by these details.





Repeated use of standard system components: ingenious solutions increase the versatility of individual components.



A single articulated panel for inside and outside corners reduces the number of different components.



TRIO is ideal where extremely flat surfaces are required

#### TRIO satisfies highest demands on evenness.

With panel height of 2.70 m: 81 kN/m² uniformly distributed load, line 6, Table 3, DIN 18202 67.5 kN/m<sup>2</sup> triangular load, line 7, Table 3, DIN 18202

With panel height of 3.30 m: 83 kN/m² uniformly distributed load, line 6, Table 3, DIN 18202 82.5 kN/m2 triangular load, line 7, Table 3, DIN 18202

PERITRIO has met these requirements since production start. That is why also older models of TRIO panels permit these high fresh concrete


P.S.: Send for the test report.

In practice this means: Fast concreting Smaller deflections




**geprüft**durch neutrales Prüfinstitut

# **G**üteschutz**v**erband Beton**s**chalungen



TRIO panels have connection holes for accessories in all struts.



**Connection holes everywhere** with securely fitted sleeves in the TRIO panels. Accessories such as push-pull props and concreting scaffolds can be used wherever they are needed.



Push-pull prop and kicker brace on horizontal or vertical strut.



Scaffold brackets on horizontal or vertical strut.

TRIO-L (aluminium) TRIO 330 TRIO Structure







# TRIO column

# Adaptable and versatile, TRIO for all applications

# PERI TRIO for all projects

The universal panel formwork that is versatile in application. For small and large contractors alike.

It doesn't matter where:
Housing projects
Industrial structures
Transport Infrastructures
Special projects
etc, etc ...



Housing projects







TRIO Repliable TRIO Housing







Retaining walls Circular structures



Sewage works



Special projects



TRIO on climbing brackets



13.20m high wall



Single sided formwork

With large hire depots



# PERI offers more than just the formwork



With our experienced representatives


Cost-cutting design and site aids

Our service ensures that your site can operate at maximum efficiency.

# The training video



The TRIO poster and brochures



Prompt, 24 hour, delivery service






On-site Instruction











Through formwork design in our technical office




Through 3D cycle planning in ELPOS and PERICAD





With the PERI panel cleaning machine





Through the Repair and Reconditioning Service.

# Standard details

# Corner, T-junctions, infills

#### **Corners**

The 60 and 72 panels form the external corner for all standard wall thickness from 180 to 400mm.

#### Basic rules for corners:

#### **External corner:**

with TR 60 and TRM 72 panels **Internal corner**:

with TRIO TE corner


# TRIO WDA 5 or WDA 6 wall thickness compensator, or timber to adjust for wall thickness variation


without WDA for 300mm WDA inside for < 300mm WDA outside for > 300mm

#### **Connection:**

With TRIO BFD alignment coupler.

5 BFD Couplers are required at 2.70 m formwork height.







# **T-junctions**


# **Basic rules for T-junction:**


## **Outside formwork:** TR 90 panel

Inside formwork:

TRIO TE corner

## TRIO WDA 5 or WDA 6 wall thickness compensator, or timber to adjust for wall thickness variation







#### 2. Reusable for maximum cost-effectiveness

Infills from 60mm to 360mm with the Filler Plate LA.


# 3. The cleanest solution

With TRIO Filler Support TPP and plywood cut to size on site.




# Standard details

# Wall offset, oblique angle, stopend



The TRM 72 multi panel, standard component for forming wall offsets.





TRIO stopend panel for 240mm thick wall.


With internal tie (in 270 x 240 large panel or TRM 72 multi panel).

The TRIO stopend tie in combination with the TAR 85 compensation waler holds stopends in position.



# **Oblique angles**

With the TGE articulated corner - for inside and outside - and the TRM 72 universal panel.





135°

The rows of holes are at the same height as the standard tie positions.

#### Basic rules for oblique angles Details relate to a panel height


Details relate to a panel height of 2.70m

# Internal articulated corner:


Four BFDs

#### **External articulated corner:**

Six BFDs Two TAR 85 walers







# Care, cleaning and maintenance

Keeps your formwork serviceable year after year

#### Care


Formwork elements must be cleaned and cared for to keep them cerviceable and maintain their value over a long period.

Hard use makes occasional repairs unavoidable.

#### PERI BIO Clean, the rapidly biodegradable release agent for all forms.

- Manufactured on a mineral oil basis
- Water Pollutant Class 1
- Acts as a penetrating oil to regenerate formwork surfaces contaminated with resin
- Allows threads to operate smoothly
- Protects timber components against rot, and construction equipment and machinery against rust

**Consumption:** 1 litre covers 50 to 90m<sup>2</sup> of formwork



PERI recommends the use of **BIO CLEAN**, the environmentally friendly concrete release agent, to ensure the formwork can be cleaned quickly and easily.

# NB Apply thinly and evenly



20 L

208 L

Can

Drum



Weight

0.91/L

0.91/L

kg:

Item

031440

031455

#### **Cleaning**

PERI's special machine cleans panels of any width, from 300mm to 3.30m in height, and up to 180mm thick.

The latest technology ensures efficient, economical cleaning. Dust extraction, continuously adjustable feed rate and individually adjustable brush pressures ensure thorough yet gentle cleaning.



PERI's cleaning machine in operation.



Removing the rivets and cleaning the frame.

#### **Maintenance**

# Even the best formlining eventually has to be replaced.

PERI also takes responsibility for disposing of all of the non-reusable parts in an ecologically sensitive manner.


PERI offers a special reconditioning service for panels subjected to hard use:

#### Minor repair service

Thorough cleaning, fitting of new sheets of plywood

#### Major repair service

Sandblasting of frames, alignment checking, welding if necessary. Renewing frame's powder coating. Fitting new sheets of plywood



Sealing of site drilled tie holes and repair of major damage is carried out with end grain plugs or plywood repair discs.





This machine rivets the new formlining into the cleaned panel frame accurately. The edge joints are filled with silicone.



The diameter of 60mm allows even major damage to be repaired.



Apply glue and hammer plywood repair disc into place.

PERI's service is particularly advantageous for the contractor when personnel and time are at a premium.

# Transportation, Handling and Storage

# Working safely with TRIO

Extremely slow shuttering and damage to the formwork are the result of sites like this:



Time and motion improvements can slash costs. Loading and unloading in the yard, on site, and moving from one part of the site to another, are major cost factors.


PERI's range therefore includes special accessories for transportation, handling and storage of standard TRIO components.




Shifting a stack of panels with TRIO galvanised stacking devices and TRIO combination lifting gear.

#### TRIO combination lifting gear

Safe working load up to 2000 kg with chains at an angle of 45°. The pins are used for shifting stacks of panels near ground or slab level. TRIO lifting hooks or TRIO galvanised stacking devices can be connected to the hooks.



Combination lifting gear in conjunction with lifting hooks during shuttering.



**The TRIO stacking device**Safe working load 500kg/device.
For stacking 5 TRIO panels of any size safely.



TRIO panels stacked neatly and compactly.



PERI pallets and crates are available for a wide variety of applications to allow safe, orderly stacking in the yard and on site.

All pallets are suitable for lifting with the crane and moving with forklift trucks.

Easily identified lifting eyes allow safe and efficient lifting with the crane


Lorry turnaround is improved by faster loading and unloading.

Compact and efficient storage.

Hot dip galvanised or powder coated welded all-steel construction for long life.

# Crate pallet 80x120/K

Item no 065016, safe working load 1500kg. For handling objects that are difficult to stack.



Post pallet

RP 80 x 120 Item no.: 025640 RP 80 x 150 Item no.: 025630 Safe working load 1500kg Crate palett 80x120 filled with 160 TRIO BFD alignment couplers.

The stacked items in the photographs are only examples. Provided the individual safe working loads are not exceeded, the pallets and crates may be loaded with other items.

# **SAFETY PRECAUTION!**

All 4 chains of the lifting gear must be used when moving the pallets with the crane.



RP 80 x 150 post pallet, stacked with twenty TRG 80s, being lifted with the crane.



PERI post pallets can be shifted easily with a fork-lift truck.

# Safety from the outset

# TRIO safety precautions

# Our product development always gives top priority to the safety of site personnel.

The following precautions are to be adopted when using PERITRIO panel formwork.

#### Handling large panels

The local safety regulations and professional codes of practice must always be followed.



#### **TRIO lifting hook:**

Quick and easy handling

Self-locking


Can be released from the slab or ground with a tie rod or board



Instructions for using the TRIO lifting hook safely.

#### Push-pull props and kicker braces

are to be arranged as shown on the adjacent diagram and specified in the table below. The first panel must always be braced with 2 push-pull props, and subsequent ones according to the following table. They are connected to the panel with the TRIO brace connector. Fixing to the slab with the matching base plate and PERI anchor bolt MMS 20x130.



# The safe working load

of the TRIO lifting hook is 1.5 t with a maximum angle of inclination of 30°.

Always follow the instructions for the use of this hook!


# PERI Push-Pull-Props and Kicker Braces


Formwork hoight <b>h</b> [m]	picture 1						picture 2				
Formwork height <b>h</b> [m]	3.0	4.0	5.0	6.0	7.0	8.0		9.0	10.0	11.0	12.0
Allowable prop spacing [m]	3.53	2.73	2.19	1.82	1.58	1.42		1.93	1.67	1.49	1.35
Actual prop load <b>F</b> <sub>RS</sub> [kN] at maximum prop spacing	9.7	9.7	9.8	9.8	9.8	9.6	F <sub>RS1</sub>	9.4 9.5	11.3 8.5	11.3 9.3	11.3 10.1
Actual kicker load <b>F</b> <sub>AV</sub> [kN] at maximum prop spacing	2.1	2.3	2.2	2.2	2.3	2.6		2.6	2.3	2.1	1.9
<b>x</b> = Dist. of base plate [m] from front face of formwork	1.2	1.6	2.0	2.4	2.9	3.5	X <sub>1</sub> X <sub>2</sub>	4.3 2.6	4.7 2.6	5.3 2.8	5.9 3.0
y = *Top connection point [m] from top of formwork	1.0	1.2	1.5	1.8	2.0	2.0	<b>y</b> <sub>1</sub> <b>y</b> <sub>2</sub>	1.5 4.5	1.8 5.5	1.8 6.2	1.8 6.9

<sup>\*</sup>If necessary, the distance from top of formwork must be adapted to the system.


A maximum force of 11.3 kN is to be led into the building at the foot of the push-pull-prop for the given width of influence.

Wind loads:  $h < 8 \text{ m} = 0.5 \text{ kN/m}^2$  $8 \text{ m} < h < 20 \text{ m} = 0.8 \text{ kN/m}^2$ 









# **Safe Concreting**

# TRIO concreting platform and concreting scaffold brackets

#### TRIO concreting platform

# Concreting is faster with the TRIO platform.




Instead of the usual laborious procedure (mount brackets, lay boards and connect rear safety handrail system), with the TRIO concreting platform the formwork is ready for concreting immediately:

- Raise concreting platform, suspend from the crane and mount.
- The 1.25m wide boarding offers sufficient space.
- The level of the platform boards, 330mm below the top of the formwork, allows you to work in comfort.

# Work is safer with the TRIO concreting platform.



 Raise safety handrail and lock with captive pins.



1466

An individual TRIO platform unit folds up so that it is only 320mm high. Each additional one stacked on top only adds 170mm.

Thus 13 stacked TRIO concreting platforms (35m run) are within a lorry's maximum loading height.



Lift mounting beams – they engage automatically.



3. Attach concreting platform to 4 chains of lifting gear at the yellow connection points.



#### **TRIO** scaffold brackets


# TRIO TRG 80 and 120 concreting scaffold brackets

- Universal design that can be used on either vertical or horizontal struts.
- Once mounted, locks automatically without additional pins etc.
- Maximum allowable spacing 1.35m with a uniformly distributed imposed load of 150kg/m²



# TRIO TRG 100/112 concreting scaffold bracket


- For mounting on horizontal and vertical struts.
- Mounting on the top strut allows the boards to project to the front edge of the formlining.
- The HANDSET HSGP handrail post is used to hold the handrails.
- Maximum permissible spacing 1.35m with a uniformly distributed imposed load of 150kg/m².




Connection to vertical strut

Connection to horizontal strut










# **Foundations**

# Shuttered with standard TRIO system components

# Column pad footings with TRIO foundation strap and AH-2 tie bracket.

The TRIO foundation strap allows the panels to be fixed in a "windmill" configuration. This saves expensive custom filler panels, since the panels can be adjusted continuously to any dimension required.



TRIO foundation strap Item no.: 023800



AH-2 tie bracket Item no.: 023630





The foundation strap in combination with the tie bracket ensures accuracy on very large foundations.



TRIO foundation strap and tie bracket act in combination for large foundations.



All sizes of foundation can be formed. The foundation strap and tie bracket allow continuous adjustment of the formwork.


TRIO foundation strap for connecting formwork quickly at external corners, with continuously adjustable panel overlap.



#### Wall footings and column pad footings with the TRIO foundation tie spanner and perforated foundation tie.

The TRIO foundation tie spanner for shuttering foundations quickly and easily. Replaces the bottom tie, saves working space and hence excavation.

Foundations up to 1.20m deep are possible with the foundation tie spanner. (Two ties provided in 2.70m length of panel).



When the tie holder is used for the top tie, the TRIO panels do not have to be exactly aligned. The panel can be tied at any position.

# TRIO foundation tie spanner Item no.: 023010





# The TRIO foundation tie spanner brings major advantages:

Dispenses with bottom tie position.

Accurate tensioning with a selfcleaning hexagonal spindle.

The small amount of working space required reduces earthworks to a minimum.



The TRIO foundation tie spanner is tensioned with a standard 14mm ratchet spanner.

Wall footing of a factory building shuttered using foundation tie spanners.

# Single face walls

# With TRIO and PERI SB brace frames

TRIO extended to 3.90m with SB-B and SB-C brace frames.

TRIO panels with PERI brace frames are used when concreting against existing walls, rock faces or sheet piling.

**PERI brace frames** for varying pour heights up to 8.75m, with an allowable fresh concrete pressure of up to 60 kN/m<sup>2</sup>.

**PERI SB-A, B, C brace frames** are designed to suit lorry and container loading dimensions.

**PERI brace frames** can be used with all PERI wall formwork systems (TRIO, VARIO, RUNDFLEX) using standard system connection components.

**The PERI V anchor brackets**For installing anchors quickly and accurately when using brace frames.




The PERI V anchor bracket is available for DW 15, 20 and 26 anchor rods. When the bracket is placed horizontally the anchor rods are inclined at the correct angle of 45°.



The choice of anchorage system is governed by the tension forces at the brace frame's anchor point.

The following points must be carefully observed when using PERI brace frames.

- 1. The structural members (eg foundations or floor slabs) must be able to withstand the tension and compression forces arising. These members must be checked accordingly at the design stage, and the position of the anchors approved.
- 2. The "other side" of the single face formwork (existing walls, sheet piling, rock faces etc) also has to be able to withstand the fresh concrete pressure.
- 3. The DW anchor rods used must not be welded or bent. We recommend using PERI's anchor bracket for positioning the anchors.




Instructions and details are given in the PERI SB Brace Frame brochure.



SB-2 brace frame with 5.40m high TRIO.



The TRIO formwork is connected to the SB brace frame with the TRIO/SB-A,B,C connector





The following connection components are used to connect TRIO to PERI SB-A, B, C brace frames:



# **Shafts**

moved as a complete unit with TRIO shaft panels TSE

# The TRIO shaft panels TSE enable the complete shaft formwork to be moved as a single unit.

When lifting the TRIO shaft panels TSE the inner formwork reduces in width by 60 mm.


This provides a striking space of 30 mm on all sides. Enough clearance to remove a complete unit.


# Remark:


The TRIO shaft panels TSE **must** be drawn out sequentially. The formwork unit is then lifted with a 4-way crane sling.

Loading per shaft panel = 2000 kg

The TRIO shaft panel TSE is supplied in 3 heights, 1.20 m, 2.70 m and 3.30 m









Complete shaft formwork hanging on the crane.

# The size of the shaft is principally of no importance for the use of the shaft panel TSE.

There is a minimum construction length of 1.30 m. The maximum size is dependent on the loading capacity of the crane hook of 2000 kg per shaft panel.

The striking space of about 30 mm in width is clearly seen. The shaft panel itself remains close to the concrete for better striking.



# Striking with the TRIO shaft panel TSE

Clearly visible: The withdrawn TRIO shaft panel TSE





For easy striking (loosening the formwork from the concrete) a formwork tool is pressed upwards, and to erect is pressed downwards.



With rectangular cross-sections the chains on the long sides must be shortened. This ensures that when lifting with the crane, all 4 shaft panels are lifted equally.




# **High Walls**

# Using TRIO without additional stiffeners

All that is needed to extend the formwork to a height of 5.40m is the BFD alignment coupler.

With PERI's TRIO you can shutter any height of wall, from 600mm wall footings to 12.0m high factory walls.

Alignment coupler and struts all round make extension with TRIO simpler.






## **CAUTION!**

Do not exceed the safe working load of the TRIO lifting hook when shifting large panel units.









Extended units up to 8.10m in height (three 2.70m panels) can be erected in one piece.





Two TAR 85s and two BFDs are needed to extend to a height of 8.10m.





Just one component: the TAR 85 compensation waler.



The TAR 85 compensation waler is easily fixed, without the need for loose clamps that can be lost.

# **Circular Structures**

# Polygonal shuttering with TRIO

Circular structures with small or large radii can be shuttered as polygons by choosing panels of the correct width.

The continuously adjustable BFD alignment coupler always allows the correct infill between the panels. This ensures that the circle can be closed, and the inside and outside panels are aligned to fix the through ties.



The diameter to be formed dictates the size of panel required.



Stormwater tank with a diameter of about 18m, shuttered with TRIO TR 270  $\times$  90 panels.



# Table of minimum radii for TRIO panels.

Panel width	R Min radius	S Deviation from curve
TR 30	3.55 m	4 mm
TR 60	6.90 m	7 mm
TR 72	8.25 m	8 mm
TR 90	10.25 m	11 mm
TR 120	13.60 m	14 mm
TR 240	26.95 m	28 mm
TR 270	30.30 m	31 mm

# 

# Notes on using TRIO as polygonal circular formwork:


- **1.** To ensure the BFD coupler can be attached properly, the maximum angular deviation of the panels must not exceed 5.2°.
- 2. To enable the ties to be fitted radially (passing through the filler timber), the smallest dimension of the inside filler timber must not be less than 40mm.
- **3.** The maximum width of the filler timber:

BFD alignment coupler → 100mm 38 alignment coupler → 260mm

When using the formwork in this way the BFD alignment coupler must **not** be positioned on the struts.



Note: The BFD alignment coupler is not positioned on the struts as normal.





Sewage tank shuttered with TRIO TR 270 x 60 panels.


# **Climbing Formwork**


# TRIO on work platforms and climbing scaffolding

# On FB 180 folding platform

TRIO formwork up to 5.40m high can be erected and supported on the FB 180 folding platform.








TRIO 330 on FB 180 folding platforms

# On ASG 160 work and access platform system

TRIO formwork up to 5.40m high can be propped using the ASG wall scaffold hinge. The weight of the formwork must be supported on the floor slab at this height extension.

**Detail:** ASG 160 mounted on ASG wall scaffold hinge.







### On KGF 240 climbing bracket

For high structures TRIO is combined with climbing brackets.

The formwork is then connected to the scaffold, and can be moved as a unit.

The TRIO articulated joint connects the TRIO to the KGF climbing brackets.





PERI



Climbing formwork units comprising TRIO panels and climbing platforms are raised one storey at a time. This ensures each step of the operation is safe, and speeds up the process by minimising crane lifts.

### On CB 240 climbing bracket




TRIO 270 on CB 240 climbing brackets




The height of the TRIO formwork is adjusted with spindles.

Varying the height of the panel using the adjusting unit (connection between TRIO and CB)

## Mounting of KGF 240/KG 180 with WGS wall scaffold hinge




## Mounting of CB 240 and CB 160 with 15 scaffold mounting ring



# **Special Applications**TRIO for beams, tunnels, custom solutions

Small beams with TRIO. Supported with MULTIPROPs.









Complete TRIO unit 8.40m high. Inside and outside formwork hung from a portal frame traveller.




Heavy beams with TRIO.




Rectangular tunnel with standard TRIO components.








TRIO for pitched roofs
The slope angle was formed using articulated corners and special walers. The vertical forces were transferred by means of walers and push-pull props.







Internal corner with

### **Column projection**

25 15





### TRIO-L (aluminium)


## The aluminium system to complement TRIO (steel)

TRIO-L is a complete system for all sites without a crane, as well as an appropriate way of supplementing red steel TRIO on any site.


**TRIO-L** is fully compatible with steel TRIO.

**TRIO-L** panels are available in the following sizes: height 2.7m, widths 900, 600 and 720mm; height 900mm and widths 1200, 600, 300 and 720mm.

**TRIO-L** is a lightweight aluminium system colour-coded yellow for ease of identification. It can be identified quickly and erected by hand whenever the crane is tied up on other work.



Filler with Compensation Waler TAR 85 and Filler Plate LA.



No extra accessories TRIO-L uses the same accessories as the red steel TRIO.



TRIO L allows shuttering to be erected without the use of a crane. Particularly advantageous on housing projects.



**TRIO-L** is a complete system for shuttering without a crane.



**TRIO-L** elements are the same size as TRIO steel panels to enable the two systems to be combined.

**TRIO-L** panels are designed for the same fresh concrete pressure as steel TRIO.

Complete cellar for a detached house shuttered with TRIO-L without the use of a crane.



TRIO-L being used to shutter foundations.



A site with TRIO-L (aluminium) and TRIO steel. The corners and infills are shuttered with TRIO-L by hand and the crane is only needed for the large steel elements (270  $\times$  240).

### **TRIO 330**

## The panel formwork for storey heights of up to 3.30m

TRIO 330 is a complete formwork system with only 6 panel sizes.

TRIO 330 can be positioned both symmetrically and asymmetrically enabling the ties to be installed with the formwork upright or on its side. This prevents incorrect tie positioning for the asymmetrical configuration.


TRIO 330 also needs only one coupler: The BFD alignment coupler fastens aligns and tightens.




2 TRIO 330 minimises deflection under high fresh concrete pressures. \*With only 2 ties in a height of up to 3.30m TRIO 330 complies with DIN 18202, Table 3, line 7 under a fresh concrete pressure of 82.5kN/m<sup>2</sup>.

3 TRIO 330 can also be extended, the symmetrical tie arrangement ensuring correct tie alignment.

\*These values have been worked out in accordance with the guidelines for obtaining the seal of approval for panel formwork from the German Association for Concrete Formwork Quality Assurance (GSV).



3





**TRIO 330** 

Showing clearly that only 2 ties are needed in a height of 3.30m.





13.20m high wall with 4 x 3.30 TRIO panels.



## Details solved in the same way as with TRIO 270


eg the external corner





Accessories such as the BFD alignment coupler, compensation waler, and scaffold brackets as the same as for TRIO 270.

TRIO 330 has all the advantages of the TRIO formwork system, such as powder coating, complete edge struts, and closed sections.



### **TRIO Structure**

# The panel formwork for special fairfaced concrete finishes

TRIO Structure, the formwork for special concrete surfaces. Any formlining required can be mounted on the fixing board.

**TRIO Structure** is available in heights of 3.30, 2.70 and 1.20m and is supplied with a factory fitted 21mm fixing board.

#### Ready-for-use Service

PERI can supply TRIO Structure with the formlining required ready fixed. If fixing is to be carried out on site we can supply the formlining required, cut accurately to size.


## **TRIO Structure - special panels** TRIO Structure panels can also be supplied in special sizes.



Panel units up to 9m wide and 2.70m high fitted with large formlining sheets.




135° corner panel, fitted with large formlining sheets, being used in the construction of a Hotel.



## Another important advantage:

TRIO's modest overall thickness is an important advantage, particularly when building narrow lift shafts or stairwells. It leaves enough space for personnel to work in.

TRIO Structure on the inside wall face is also often combined with TRIO on the outer face or vice versa, where a special concrete finish is only required on one side of a wall.



# All of the advantages of TRIO framed formwork are combined

TRIO Structure with board finish formlining being used to construct a bridge abutment.

A high permissible fresh concrete pressure of up to 80kN/m² allows faster concreting.

#### **Compact for transportation**

in TRIO Structure


TRIO Structure's overall thickness of 140mm is 60% less than girder formwork. This cuts your transportation and storage costs, speeds up loading and unloading in your yard and on site.

#### **Assembling TRIO Structure**

The formlining required can be fixed from the front (using screwnails) or from behind (with Torx screws). Other types of fixing are available on request.

# **Example**Bridge abutment





### TRIO column formwork

## With panels for walls and columns

## TRIO TRS column panels are designed to supplement TRIO.

They can be used as a column panel for cross sections up to 750 x 750mm or as a "standard" 90 panel in wall formwork.

The TRIO column panels have tie holes in the frame and can be used as 90cm wide TRIO standard wall panels.


The permissible fresh concrete pressure to DIN 18218 is 100kN/m<sup>2</sup>.

Accessories such as push-pull props connect in the same way as for TRIO formwork.


## Chamfer strip for TRIO column formwork with clamping mechanism.

Difficult, laborious nailing of chamfer strips is now a thing of the past.

Just push them on!




# Detail \_\_\_\_



## The PERI concreting platform for TRIO column formwork.

Continuously adjustable for any cross section from 200 x 200 to 750 x 750mm.



PERI's concreting platform also fits RAPID and QUATTRO column formwork. The telescopic support allows continuous adjustment to any column cross section up to  $750 \times 750$ mm.




TRIO column formwork to a height of 4.5m with concreting platform.




#### **Ladder access for PERI TRIO** column formwork.

Ladder safety cage 150 Ladder safety cage 75


Item no.: 051450 Item no.: 104132






Ladder 180/6 Access ladder 180/2

Item no.: 051410 Item no.: 103724





Item no.: 103362




Ladder hook Ladder base

Item no.: 103718 Item no.: 051460







Complete 5.40m high TRIO column formwork. With concreting platform, ladder access and push-pull props.

### **PERI International**



#### 01 PERI GmbH

Rudolf-Diesel-Strasse 89264 Weissenhorn info@peri.com www.peri.com



#### 02 France

PERI S.A.S. 77109 Meaux Cedex peri.sas@peri.fr www.peri.fr

#### 03 Switzerland

PERI AG 8472 Ohringen info@peri.ch www.peri.ch

#### 04 Spain

PERI S.A. 28110 Algete - Madrid info@peri.es www.peri.es

#### 05 Belgium/Luxembourg

N.V. PERI S.A. 1840 Londerzeel info@peri.be www.peri.be

#### 06 Netherlands

PERI B.V. 5480 AH-Schijndel info@peri.nl www.peri.nl

#### **07** USA

PERI Formwork Systems, Inc. Elkridge, MD 21075 info@peri-usa.com www.peri-usa.com

#### 08 Indonesia

PT Beton Perkasa Wijaksana Jakarta 10210 bpw@betonperkasa.com www.peri.com

#### 09 Italy

PERI S.p.A. 20060 Basiano info@peri.it www.peri.it

#### 10 Japan

PERI Japan K.K. Tokyo 103-0015 info@perijapan.jp www.perijapan.jp

#### 11 United Kingdom/Ireland

PERI Ltd. Rugby, CV23 0AN info@peri.ltd.uk www.peri.ltd.uk

#### 12 Turkev

PERI Kalip ve İskeleleri Esenyurt / İstanbul 34510 info@peri.com.tr www.peri.com.tr

#### 13 Hungary

PERI Kft.. 1181 Budapest info@peri.hu www.peri.hu

#### 14 Malaysia

PERI Formwork Malaysia Sdn. Bhd. 43300 Seri Kembangan, Selangor Darul Ehsan info@perimalaysia.com www.perimalaysia.com

#### 15 Singapore

PERI ASIA Pte. Ltd Singapore 387355 pha@periasia.com www.periasia.com

#### 16 Austria

PERI Ges.mbH 3134 Nußdorf ob der Traisen office@peri.at www.peri.at

#### 17 Czech Republic

PERI spol. s r.o. 252 42 Jesenice u Prahy info@peri.cz www.peri.cz

#### 18 Denmark

PERI Danmark A/S 2670 Greve peri@peri.dk www.peri.dk

#### 19 Finland

PERI Suomi Ltd. Oy 05460 Hyvinkää info@perisuomi.fi www.perisuomi.fi

#### 20 Norway

PERI Norge AS 3036 Drammen info@peri.no www.peri.no

#### 21 Poland

PERI Polska Sp. z o.o. 05-860 Płochocin info@peri.pl.pl www.peri.pl.pl

#### 22 Sweden

PERIform Sverige AB 30013 Halmstad peri@periform.se www.periform.se

#### 23 Korea

PERI (Korea) Ltd. Seoul 135-080 info@perikorea.com www.perikorea.com

#### 24 Portugal

PERIcofragens Lda 2790-326 Queijas info@peri.pt www.peri.pt

#### 25 Argentina

PERI S.A. B1625GPA Escobar – Bs. As. info@peri.com.ar www.peri.com.ar

#### 26 Brazil

PERI Formas e Escoramentos Ltda. Vargem Grande Paulista São Paulo info@peribrasil.com.br www.peribrasil.com.br

#### 27 Chile

PERI Chile Ltda. Colina, Santiago de Chile peri.chile@peri.cl www.peri.cl

#### 28 Romania

PERI România SRL 077015 Baloteşti info@peri.ro www.peri.ro

#### 29 Slovania

PERI Slowenien 2000 Maribor peri.slo@triera.net www.peri.com

#### 30 Slovakia

PERI spol. s r.o. 903 01 Senec info@peri.sk www.peri.sk

#### 31 Australia

PERI Australia Pty. Ltd. Glendenning NSW 2761 info@periaus.com.au www.periaus.com.au

#### 32 Estonia

PERI AS 76406 Saku vald Harjumaa peri@peri.ee www.peri.ee

#### 33 Greece

PERI Hellas Ltd. 194 00 Koropi info@perihellas.gr www.perihellas.gr

#### 34 Latvia

PERI SIA 2118 Salaspils novads, Rigas rajons info@peri-latvija.lv www.peri-latvija.lv

#### 35 United Arab Emirates

PERI (L.L.C.) Dubai perillc@perime.com www.perime.com



#### 36 Canada

PERI Formwork Systems, Inc. Bolton, ON - L7E 1K1 info@peri.ca www.peri.ca

#### 37 Lebanon

Lebanon Representative Office Jdeideh lebanon@peri.de www.peri.de

#### 38 Lithuania

PERI UAB 02300 Vilnius info@peri.lt www.peri.lt

#### 39 Morocco

PERI S.A. Tanger peri25@menara.ma www.peri.com

#### 40 Israel

PERI Formwork Engineering Ltd Petach Tikva, 49002 info@peri.co.il www.peri.co.il

#### 41 Bulgaria

PERI Bulgaria EOOD 1839 Sofia peri.bulgaria@peri.bg www.peri.bg

#### 42 Iceland

Armar ehf. 220 Hafnarfjörður www.armar.is

#### 43 Kazakhstan

TOO PERI Kazakhstan 050059 Almaty peri@peri.kz www.peri.kz

#### 44 Russian Federation

OOO PERI 142407, Noginsk District moscow@peri.ru www.peri.ru

#### 45 South Africa

Wiehahn Formwork and Scaffolding (Pty) Ltd. 7600 Stellenbosch info@wiehahn.co.za www.wiehahn.co.za

**46 Ukraine** TOW PERI Ukraina 07400 Brovary peri@peri.ua www.peri.ua

#### 47 Egypt

Egypt Branch Office 11361 Heliopolis / Cairo info@peri.com.eg www.peri.com.eg

#### 48 Serbia

PERI Oplate d.o.o. 11272 Dobanovci office@peri.rs www.peri.rs

#### 49 Mexico

PERI Cimbras y Andamios, S.A. de C.V. Estado de México, info@peri.com.mx www.peri.com.mx

#### 50 Azerbaijan

PERI Kalıp ve İskeleleri Baku peribaku@peri.com.tr www.peri.com.tr

#### 51 Turkmenistan

PERI Kalıp ve İskeleleri Aşgabat ahmet.kadioglu@peri.com.tr www.peri.com.tr

#### 52 Belorussia

PERI Belarus 220030 Minsk info@peri.by www.peri.com

#### 53 Croatia

PERI oplate i skele d.o.o. 10 250 Donji Stupnik/ Zagreb info@peri.com.hr www.peri.com.hr

PERI GmbH Iran Branch Office Tehran info@peri.ir www.peri.ir

#### 55 India

PERI (India) Pvt Ltd Mumbai - 400064 info@peri.in www.peri.in

#### 56 Jordan

PERI GmbH - Jordan 11947 Amman jordan@peri.com www.peri.com

#### 57 Kuwait

PERI Kuwait 13011 Kuwait kuwait@peri.com www.peri.com

#### 58 Saudi Arabia

PERI Engineering Division of Jamjoom Consult Saudi Árabia 21463 Jeddah info@peri.com.sa www.peri.com.sa

#### 59 Qatar

PERI Qatar LLC P.O.Box: 31295 - Doha info@periqatar.com www.periqatar.com

#### 60 Algeria

Société PERI S.A.S. Kouba - Alger peri.alger@peri.fr www.peri.fr

#### 61 Albania

PERI Sh.p.k. Tirane erti.hasanaj@peri.com.tr www.peri.com.tr

#### 62 Peru

PERI Peruana SAC Villa El Salvador, Lima contacto@peri.com.pe www.peri.com.pe

#### 63 Panama

PERI Panama Inc. 0832-00155 Panama City info@peri.com.pa www.peri.com.pa

#### 64 Angola

PERIcofragens, Lda. Luanda renato.portugal@peri.pt www.peri.pt

#### 65 Nigeria

Heights Access Nigeria Ltd. Victoria Island, Lagos info@heightsaccessng.com www. heightsaccessng.com

#### 66 Oman

PERI (L.L.C.) Muscat perimct@perime.com www.perime.com

## The optimal System for every **Project and every Requirements**



Wall Formwork



Column Formwork



Slab Formwork



**Climbing Systems** 



**Tunnel Formwork** 



Bridge Formwork



**Shoring Systems** 



**Construction Scaffold** 



Facade Scaffold



**Industrial Scaffold** 



Access



**Protection Scaffold** 



**System-Independent Accessories** 



Services



PERI GmbH Formwork Scaffolding Engineering P.O. Box 1264 89259 Weissenhorn

89259 Weissenhorn Germany Tel. +49 (0)7309.950-0 Fax +49 (0)7309.951-0 info@peri.com www.peri.com